



Sustainability Worldwide Georgia Tech



Introduction: Three Alliance Center is located in the heart of Buckhead (3500 Lenox Rd NE). The building is 30 stories and provides the community with 502,000 ft.² of office space. Although this property is LEED Gold certified, our group was able to identify two specific initiatives to present to the property management team (Transwestern) for carbon emissions reduction. Given Transwestern's commitment to sustainability, we believe these initiatives are within their strategic alignment.


LED Lighting Efficiency

Problem: Currently there are incandescent fixtures located in all common corridors, restrooms, elevator vestibules, the fitness center, main conference center, lobby and tenant lounge (2,400 total fixtures).

Solution: Incandescent LED Fixtures Our team plans to assist with moving the fixtures to LED as the sole source of

lighting at 3AC.

Total CO₂ Reduction: 1,845,486 lbs.



1.845.486.72 lbsCO=

83.71 Ford Fusions

Removed from the

Carbon Calculation based on kWh usage moving from 144 kWh/day to 9.6 kWh/day for 2,400 total fixtures.

One-Time Project Cost:

\$43,176

NPV: \$662.902

ROI: 1,435%

IRR: 353%

HVAC Demand Ventilation

Problem: No control method currently in place to modulate the volume exchange of fresh air into an enclosed space of Three Alliance by the HVAC unit.

Solution: Demand Controlled Ventilation will include adding sensors to measure the individuals (density) per floor to calculate the specific load of <u>HVAC that needs to be</u> emitted per floor.

Total CO₂ Reduction: 443,576 lbs.



from the Road!

Carbon Calculation based on total building energy consumption being reduced by 5%.

Financial Impact:

One-Time Project Cost: \$50,250

Payback: 1.37 years

NPV: \$120,243

ROI: 139% 443,575.62 lbsCO= 20.12 Ford Fusions Removed IRR: 67%

Co-Benefits

- Potential for tenant retention
- Maintain or improve LEED status
- Potential to charge higher rents as the building moves towards a higher level of efficiency
- Increase engineers' productivity with less focus on HVAC & lighting

2x2 Stakeholder Analysis

Key Stakeholders	Involvement
	Will be making the final decision to adopt the new
Tenants	light bulbs. Have not been involved up to this point,
	Low involvement. Instructed the Transwestern to do
Buildng Ownership	more sustainabilty initiatives.
	High involvement. Kristen Stappenbeck has been our
Property Manager	main contact, and supporter of the new plans.
	Jessee Kave was interviewed and had a moderate
	involvement. Jessee will be the one implementing
Chief Engineer	the new HVAC system.
	Not involved in the decision making process, but they
	will be affected on their day to day with the new
Building maintenance Group	projects.

Current Status/Future Plans

Team has met with the Transwestern management team to present a formal plan. Our next meeting will be to discuss the implementation timeline. Our desire is for the work to begin by 4th quarter 2018.

Financial Impact:

Payback Period: 0.28 years